



D.S. RAMI REDDY,
M.Tech.
Chief General Manager (Engg.)

**HYDERABAD METROPOLITAN WATER SUPPLY
AND SEWERAGE BOARD
OPERATION & MAINT. CIRCLE-III**
Goshamahal, Hyderabad, India

Supplemental Supply Order No: CGM(E)/O&MC.III/D5/CI Sluice Valves/2009-2010/ 755 Date 18-09-2009.

To

M/s. Super Valve Mfg. Co.,
29/2/3/1, Narasingha Dutta Road,
Kadamtala,
Howrah - 711 101.

Gentlemen,

Sub: HMWS&SB - O&M Circle-III - Procurement of 100mm, 150mm and 200mm dia CI D/F Sluice Valves, under Central Stores Division - Supplemental Supply Order issued - Regarding.

Ref: 1) DT, HMWS&SB Work Order No.1246; dt.01.08.2009.
2) T.O Agt. No.72/09-10; dt.24.08.2009.
3) Your letter dated 20.08.2009.

Your offer for supply of extended quantity of CI D/F Sluice Valves as detailed is hereby accepted for **Rs.3,387,241.65 (Rupees Thirty Three lakhs Eighty Seven thousand Two hundred Forty One and paise Sixty Five only) which is @ -40.00% less on basic** including all taxes, duties, transportation, loading, unloading and Inspection charges etc. complete as directed by the HMWS&SB Engineers. The work should be completed within the specified time of One Month in all respects.

Sl. No.	Description of Item	Quantity	Rate (Rs.)	Per	Amount (Rs.)
1	Manufacture supply and delivery of CI D/F Sluice Valves for Water works purposes (PNI) conforming to IS 14846/2000 with amendments No.1&2 heavy duty with CI grade FG 260 as per IS: 210 Two coats of primer suitable for EPOXY PAINTS finish shall be applied to all metal surface and finally two coats of Epoxy paint. The valve shall be tested for (closed end Test) against hydrostatic test requirement. The rates are including transportation, Central Excise Duty and Sales Tax as per break up given below etc. complete as directed by the HMWS&SB Engineers. The operation can be done with hand wheel / Cap ISI marked.				
a)	100mm dia PN-1.0 (Wt. of Sluice Valve = 39 Kgs / Each) (With cap)	500 Nos.	5673.00	1 Each	2,836,500.00
b)	150mm dia PN-1.0 (Wt. of Sluice Valve = 61 kgs / Each) (With cap)	200 Nos.	8509.00	1 Each	1,701,800.00
a)	200mm dia PN-1.0 (Wt. of Sluice Valve = 103 Kgs / Each) (With cap)	65 Nos.	14914.00	1 Each	969,410.00
					5,507,710.00
				Deduct T.P. @ -40.00% less	(2,203,084.00)
					3,304,626.00
				Add CST @ 2% on basic	66,092.52
				Add Inspection charges @ 0.5% on basic	16,523.13
				Total	3,387,241.65

(Rupees Thirty Three lakhs Eighty Seven thousand Two hundred Forty One and paise Sixty Five only)

Note: PAYMENT FOR TAXES AND DUTIES WILL BE MADE AS PER ACTUALS ON DOCUMENTARY EVIDENCE.


Contd..2nd..

:: 2 ::

You are requested to attend this office alongwith a Non-Judicial Stamp Paper worth Rs.100=00 (Rupees One hundred only) for concluding the agreement within seven days from the date of receipt of this order.

The receipt of this Work Order should be acknowledged.

Yours Sincerely,


CHIEF GENERAL MANAGER (ENGG.),
O&M CIRCLE-III, HMWS&SB.